

Rockmart High School Wood Storage Building

Addenda # 1

Include 124' gutters and 4-downspouts @ 16'0.

4" # 57 stone with vapor barrier

Slab will be 6" thick, smooth finish

Add 1 exterior walk thru door 3'0"x 7'0"

No electrical or plumbing in the project

School system is responsible for permits.

Basis of design on building is Dean Steel, Cedartown Ga.

Drawing and specifications are attached.

End of Addenda # 1.